
SANTA CRUZ COUNTY RTC BICYCLE ADVISORY COMMITTEE MEETING

SOQUEL DRIVE BUFFERED BIKE LANES AND CONGESTION MITIGATION PROJECT

AUGUST 9, 2021





PRESENTERS

Russell Chen, PE

Santa Cruz County Public Works

Traffic Division

Shawn O'Keefe, PE, QSD

Consultant Project Manager

Mark Thomas



EXISTING CONDITIONS



- 4-Lane Roadway (w/ 2-way left turn lane)
- High volumes and high speeds

- Transit reliability challenges and inadequate stops
- Pedestrian network gaps and ADA ramp inconsistencies




PROJECT GOALS

- Reduce traffic congestion and improve safety for all modes of travel
- Enhance multimodal options to increase corridor throughput
- Reduce greenhouse gas emissions
- Improve emergency response time
- Improve access to housing, jobs, schools and medical facilities
- Improve active transportation connectivity
- Promote sustainable development and livable communities





PROJECT **OVERVIEW**










Stop-Controlled Intersection





Existing crossing with RRFB

Install RRFB at new crossing






PROJECT FEATURES

- 3.2 miles of separated bike lanes, Class IV (2-foot buffer with delineators)
- 6.8 miles of buffered bike lanes, Class II (1-foot to 2-foot buffer)
- 28 bike boxes (one and two-stage)
- Transit signal priority and adaptive signal control at 23 intersections
- 0.6 miles of sidewalk gap closures
- 0.3 miles of sidewalk reconstruction
- 94 reconstructed ADA ramps
- 70 crosswalk upgrades
- 10 mid-block crosswalk RRFB's (rectangular rapid flashing beacons)
- Pavement rehabilitation (cape seal)






TYPICAL CROSS-SECTIONS (BUFFERED CLASS II & IV)






TYPICAL CROSS-SECTIONS (CLASS II+)



TYPICAL CROSS-SECTIONS (CLASS II w/PARKING)






INTERSECTION TREATMENTS – BIKE BOX





INTERSECTION TREATMENTS – TWO-STAGE BIKE BOX





PROJECT BUDGET

Description	Current Planned Construction Budget (MM)	Anticipated Construction Cost (MM)
SB-1 Congested Corridors Grant	\$16.5	
County Funds	\$3.5	
Conceptual Cost Estimate (Aug 2021)		\$22.8
TOTAL	\$20.0	\$22.8
SHORTFALL		-\$2.8





PROJECT SCHEDULE

- Preliminary Engineering complete September 2021
- Final Design complete February 2022
- Right of Way Acquisition complete Spring 2022
- Start Construction Summer 2022



THANK YOU!

